

PLUGGING RECORD

Instructions: Within thirty days following the plugging of a dry hole, or the abandonment of a producing well, the owner or operator shall submit this form in duplicate for wells on patented or Federal lands, and in triplicate for wells on State lands. Geological information will be held confidential for a period of twelve months if requested in writing. Fill out form as completely as possible.


Operator Clinton Oil Company					
Address 217 North Water, Wichita, Kansas 67202					
Well Number 14	Lease Name Vowers Unit		Field and reservoir (If wildcat, so state) Vowers		
Location C NE SW Sec. 33 Twp. 17N Range 54W				County Banner	
Footage Location 1980 ft. from (N) <input checked="" type="checkbox"/> line, 1980 ft. from (E) <input checked="" type="checkbox"/> line of SE 1/4					
Spud Date 4-10-56	Date reached T.D. 5-3-56	Date Plugged 2-19-72	Total Depth 6055	P. B. T. D. 6011	
Elevation 4751 GL		Reference (indicate) (KB) (GL) (DF) 4758 RDB		Producing rate on initial completion	
		Oil (bbls/day) 144	Gas (MCF/day)	Water (bbls/day)	
Application to drill this well was filed in name of: Petroleum, Inc.			Producing rate at time of abandonment		
		Oil (bbls/day) 0	Gas (MCF/day) 0	Water (bbls/day) 0	

CONDITION OF HOLE

Name each formation containing oil or gas. Indicate which formations open to well bore at time of plugging.	Fluid Content	Depth Interval	Size, kind and depth of plugs used. Indicate zones squeeze cemented giving amount of cement.
"J" Sand	Oil	5918'	Squeezed perms w/10 sacks cmt at 5950-56.

Size, kind and depth of any additional plugs
10 sacks cmt plug in & out of csg stub at 2999'. 10 sack cmt plug at base of 8 5/8" surface pipe at 558' & 10 sack cmt plug at surface.

CASING RECORD

Size casing in O. D.	Weight lbs/ft.	Setting Depth	Amount Recovered	Amount left in well	Method of parting (Spot, ripped, etc.)
8 5/8"	29.35#	558'	0	558'	
4 1/2"	9.5#	6034'	2999'	3035'	

Was hole filled with mud-laden fluid? **NO**

If this well was plugged back for use as a fresh water well, give pertinent details of plugging operations to base of fresh water sand. Attach letter from surface owner authorizing completion of this well as a fresh water well and agreeing to assume full liability for subsequent plugging which may be required.

I/We hereby swear or affirm that the statements herein made are complete and correct.

Michael A. Stand
Signature

District Engineer, Rocky Mountain District
Title

April 13, 1972
Date

(If new dry hole, complete well log on reverse side of form)